



Clifton Park, N.Y.

Gold Package

STANDARD FEATURES

CONSTRUCTION

8'x8" poured concrete walls with steel rebar reinforcement

Perimeter foundation drainage system includes:

Perforated drainage tile inside and out

Asphalt coating on all exterior foundation wall surfaces

8" stone base below basement slab

2x6 exterior wall construction on heated areas

1/2" OSB waferboard sheathing on walls and roof

Air infiltration reducing house wrap on exterior heated walls

3/4" OSB T&G sub-flooring glued and nailed

Engineered truss joist (TJI) silent floor framing system proving exceptional strength and performance

R-19 (6" batts) wall and R-38 (12" batts) ceiling insulation

Basement R11 and flamespread 25 wrap

3,000 PSI basement and 4,000 PSI garage and exterior concrete floors

Two car garage as per plan

*Waterline hook-up to refrigerator

Garage sheet rocked and one coat of tape finish

Steel insulated raised panel overhead garage door with square trim surround and glass panel with automatic door opener

GAF Timberline 30 year architectural roof shingles

Continuous roof ridge venting for full attic airflow

Maintenance free vinyl siding, aluminum fascia/vinyl soffit

Anderson Tilt-Wash low "E" vinyl clad windows with grilles and screens

Fiberglass insulated paintable (Smooth Star) front entry door with sidelites per plan

Weiser "Augusta" front door fashion brushed nickel handle set

Public water and sewer services

Underground utilities

*All information furnished above is deemed to be reliable but not guaranteed. The information is subject to errors, omissions, change of price without notice. It is your responsibility to conduct an independent investigation of the property to confirm any and all information.

MECHANICAL SYSTEMS

50 gallon direct vent gas hot water heater
Amana 96 direct vent furnace with programmable thermostat (gas forced hot air)
Amana central air conditioning
CAT 5 pre-wiring for three (3) telephones and three (3) RG6 cable TV's
200 AMP electrical service (underground)
Smoke detectors – hard wired
Carbon monoxide detector
All bathrooms to have exterior exhaust venting

INTERIOR

Professional interior decorating consultant
9' high first floor ceilings as per plan
Masonite interior doors painted white
White semi-gloss paint on all woodwork and doors
Walls and ceilings painted with antique white flat paint
Colonial style interior trim with 5" tall baseboards and 2¼" casing throughout
Wire closet shelving
Wall/wall ultra dense, stain resistant 10 year wear warranty carpet with 6 lb. pad
Oak tread staircase as per plan
Natural finish oak handrails with painted rail balusters as per plan
Glass French doors at study location as per plan
Crown molding in dining room per plan
Oak hardwood in dining room, kitchen and kitchenette as per plan
Gas burning fireplace with tile surround, flush hearth and mantle molding
Tiled foyer, laundry room and baths (\$3.50 per square foot allowance)
Lighting package allowance \$2,100.00 for inside and outside

KITCHEN

Level 2- HOMECREST 36" high wall cabinets with (1) 42" staggered corner wall with crown molding
Whirlpool self cleaning electric smooth top range #WFE361-stainless steel
Whirlpool Space maker microwave (non-venting)over range-WMH1162-stain. steel
Whirlpool dishwasher #DU1015- stainless steel
Stainless steel sink
Center island in kitchen as per plan
Granite countertops with tile backsplash(Granite to be chosen from Classic Collection or Group A)(Tile allowance TBD)
Garbage disposal, switch operated feed
Mansfield fixtures with Delta faucet

*All information furnished above is deemed to be reliable but not guaranteed. The information is subject to errors, omissions, change of price without notice. It is your responsibility to conduct an independent investigation of the property to confirm any and all information.

MASTER BATH

Ceramic tile flooring (\$3.50 per square foot allowance)
Soaking fiberglass tub as per plan
Framed shower glass door
One piece fiberglass tub/shower unit as per plan
Towel bar and paper holder in chrome
Mansfield fixtures with Delta faucet (chrome)
Mansfield toilet
Cultured marble vanity counter or custom fit laminate vanity counter with sink
Level 2- HOMECREST vanity cabinet
Vanity mirror

MAIN BATH

Ceramic tile flooring (\$3.50 per square foot allowance)
One piece fiberglass tub/shower unit as per plan
Towel bar and paper holder in chrome
Mansfield fixtures with Delta faucet (chrome)
Mansfield toilet
Cultured marble vanity counter or custom fit laminate vanity counter with sink
Level 2- HOMECREST vanity cabinet
Vanity mirror

HALF BATH - Per Plan

Ceramic tile flooring (\$3.50 per square foot allowance)
Towel bar and paper holder in chrome
Mansfield fixtures with Delta faucet (chrome)
Mansfield toilet
Pedestal sink
Vanity mirror

*All information furnished above is deemed to be reliable but not guaranteed. The information is subject to errors, omissions, change of price without notice. It is your responsibility to conduct an independent investigation of the property to confirm any and all information.

LAUNDRY ROOM

Ceramic tile flooring (\$3.50 per square foot allowance)
Electric hook-up for washer and dryer
Wire shelf in laundry area
Vent hose for dryer hook-up

EXTERIOR

Professionally coordinated custom exterior color schemes
Two exterior electrical outlets
Front and rear exterior hose connections (frost free)
Full front porches and portico porch entrances as per plan
Asphalt paved driveway
Brick paver walkway from front door to driveway
Exterior shutters and window mantels on front where shown
White clad Anderson sliding door with screen as per plan

LANDSCAPING

Professional landscape planting package
Underground lawn irrigation system installed
Lamp post
Mailbox and post installed
Grass seeding of graded areas - hydroseed

*All information furnished above is deemed to be reliable but not guaranteed. The information is subject to errors, omissions, change of price without notice. It is your responsibility to conduct an independent investigation of the property to confirm any and all information.